

PROJECT CONTROL

No.

Date.

FASE 1 Initiation (sebelum proyek jalan)

1. Feasibility Study

apakah proyek layak?

berapa kebutuhan daya?

berapa investasi

"Feasibility Report"

2. Basic Engineering

SLD

Layout

Concept design

"Basic engineering design"

3. Cost Estimation

Hitung : Equipment

Civil

Mechanical

Electrical

Manpower

"Cost Estimate"

"CAPEX Estimate"

} PAB

FASE 2 Tender / Proposal

1. Commercial Proposal

harga

Payment term

schedule

2. Technical proposal

Metodologi kerja

Scope

Spesifikasi

3. Preliminary schedule

"Level 1 schedule"

Engineering

Procurement

Construction

commissioning

LOD

Magih sangat Global

* pernah buat yg

LOK seipakem

* Disini **Project Control** mulai bekerja
No. _____ Date. _____

FASE 3 project planning

1. Tentukan scope

Dokumen :

- Contract
- BoQ
- Scope of work

} Baca semua

2. Membuat **WBS** * ini adalah pondasi !!

Contoh : * pecah milestone menjadi lebih detail

↳ 4 • Mechanical

4.1 Daily tank

4.2 Fuel pipe

4.3 Exhaust

4.4 Genset installation

3. Buat Schedule

Level 1 management schedule

seperti saat tendering

Level 2 Lebih Detail

seperti di web, u/ client

Level 3 Sangat Detail

Semi Action plan, seperti biasa dibuat

Contoh : Excavation

Level 3, gunakan

- MS Project

- Primavera P6

Lean concrete

Rebar

Formwork

concrete pouring

curing

4. Resource Planning

Hizung : • Manpower
• Equipment
• Material

contoh : Civil Supervisor = 1
Foreman = 2
Mason = 8
Helper = 10

5. Cost Planning

Muncul : Project Budget

Isinya = Direct Cost
Indirect cost

Cost Breakdown structure (CBS)

Isinya = Civil
Mechanical
Electrical
Commissioning

6. Cash Flow

Project Control Mulai bitin

Cash in (uang masuk dari owner)

Cash out (uang keluar)

↳ vendor

Gaji

Material

FASE 4 execution (proyek mulai jalan)
* disini pekerjaan Harian di mulai

1. Daily Progress

Misal : Excavation

Plan : 100 m^3

Actual : 80 m^3 (why? - Hujan deras
Pukul sekian)

2. Weekly Progress

Bikin : • Progress Report

• S-curve

3. Monthly Progress

Bikin : • Monthly Report

• Progress Claim

FASE 5) Monitoring & control

Project control membawakan

(Site Project Control)

1. Schedule

Plan Vs Actual

misal : plan : 45%

Actual : 38%

delay 7%

2. Cost

Budget Vs Actual

misal : Budget : 10 M

Actual : 11 M

over budget

3. Productivity

Contoh :

Target : 10 M pipe/day

Actual : 7 M pipe/day

FASE 6**Closing**

mengulang selesai

Dokumen: [Punch List]

↓
atau daftar pekerjaan sisa

Mechanical completion (MC)

MC

Commissioning

Testing

COD

Commercial operation date

Handover

PAC

(Provisional Acceptance Certificate)

FAC

Final Acceptance Certificate